

Force Provider (FP)

INVESTMENT COMPONENT

Modernization

Recapitalization

Maintenance



MISSION

To provide the Army, joint U.S. Military, host nation, and coalition forces personnel with a high-quality deployable base camp to support the expeditionary missions, develop, integrate, acquire, field, sustain, and modernize base camp support systems to improve the warfighters fighting capabilities, performance, and quality of life.

DESCRIPTION

Each Force Provider (FP) includes 71 deployable triple container (TRICON) systems, including eight latrine systems, eight shower systems, four kitchen system, containerized batch laundry system, four TRICON refrigerated containers, 26 60-kilowatt tactical quiet generators, 26 modular personnel tents (air supported), four 400,000 BTU water heaters, four improved fuel distribution systems, two wastewater evacuation tank/trailers, 26 mobile electric power distribution replacement systems, 56 environmental control units, and eight air compressors that are diesel engine driven and operate at 17 cubic feet per minute. Additional operational add-on

kits include a cold-weather modification system, prime-power modification system, electric kitchen, and shower water reuse system.

SYSTEM INTERDEPENDENCIES

60-kilowatt tactical quiet generator

PROGRAM STATUS

- **3QFY08:** Deployment of FP 600-man base camp, 150-man subset through urgent materiel release to support an operational needs statement (ONS)
- **4QFY08:** Deployment of two FP 600-man base camps through urgent materiel release to support ONS
- **1QFY09:** Module number 53 production initiated

PROJECTED ACTIVITIES

- **4QFY09:** Projected delivery of FP Module number 53
- **1QFY10:** Capabilities Production Document approval supporting improved capabilities
- **3QFY10:** Integration of shower water reuse system into FP baseline

ACQUISITION PHASE

Technology Development

Engineering & Manufacturing Development

Production & Deployment

Operations & Support



Force Provider (FP)

FOREIGN MILITARY SALES

None

CONTRACTORS

Force Provider Assembly:

Global Defense Engineering (Easton, MD)
Letterkenny Army Depot (Chambersburg, PA)

Expeditionary TRICON Kitchen System and FP Electric Kitchen:

Tri-Tech USA Inc. (South Burlington, VT)

Airbeam TEMPER Tent:

Vertigo Inc. (Lake Elsinore, CA)

Environmental Control:

Hunter Manufacturing (Solon, OH)

TRICON Container:

Charleston Marine Containers
(Charleston, SC)

Waste Water Evacuation Tank/Trailer:

Marsh Industrial (Kalkaska, MI)

Cold Weather Kit Assembly:

Berg Companies, Inc. (Spokane, WA)

Mobile Electric Power Distribution System Replacement:

Lex Products Corp. (Stamford, CT)

Expeditionary TRICON Systems (shower, laundry, latrine):

To be determined

